

Willamette Water Supply
Our Reliable Water



2018 TACOMA PNWS-AWWA

Long-Term Storage and Maintenance of Out-of-Service Pipelines


April 27, 2018

Agenda

- WWSP Background
- Development of Interim Operations Plans
- PLW_1.1 Example
- Water Quality Data Collection



Water Supply Program



- Modified water intake
- New water filtration plant
- Water reservoirs
- 30+ miles of large diameter pipeline
- Tualatin Valley Water District: 60% City of Hillsboro: 40%
- Scheduled completion: 2026



CORNELIUS PASS PIPELINE PROJECT
FRANCES RD TO HIGHWAY 26

PLW_2.0
(PIPELINE WEST)

3.4
MILES

CONSTRUCTION: 2021 - 2023

SOUTH BEAVERTON AREA WATER STORAGE TANKS
STORAGE TANKS

RES_1.0

CONSTRUCTION: 2022 - 2024

TUALATIN-SHERWOOD AREA PIPELINE PROJECT
SW 124TH AVE TO NORTH OF BEEF BEND RD

PLM_4.0
(PIPELINE MAIN)

5.3
MILES

PLM_A.1 HIGHWAY 99 CROSSING
(WASHINGTON COUNTY)
CONSTRUCTION: 2000 - 2021

PLM_A.2 TUALATIN-SHERWOOD ROAD
(WASHINGTON COUNTY)
CONSTRUCTION: 2000 - 2022

PLM_A.3 RDT ROGERS ROAD
CONSTRUCTION: 2022 - 2023

124TH AVENUE PARTNERSHIP PROJECT
SW 124TH AVE EXTENSION

PLM_3.0
(PIPELINE MAIN)

2.7
MILES

CONSTRUCTION: 2016 - 2018
(WASHINGTON COUNTY)

WATER TREATMENT PLANT
WATER TREATMENT PLANT (WTP)

WTP_1.0

CONSTRUCTION: 2022 - 2025


INCLUDES FINISHED WATER PUMP-STATION PROJECT (EPL_3.0)
INCLUDES DISTRIBUTED CONTROL SYSTEM PROJECT (ECS_3.0)

RAW WATER FACILITIES
RAW WATER FACILITIES (RAW)

RWF_1.0

CONSTRUCTION: 2020 - 2024

Willamette Water Supply
Our Reliable Water
PROJECTS



SOUTH HILLSBORO AREA PIPELINE PROJECT
FARMINGTON RD TO FRANCES RD

PLW_1.0
(PIPELINE WEST)

3.9
MILES

PLW_1.1 BLANTON TO TV HWY
(SOUTH HILLSBORO DEVELOPMENT)
CONSTRUCTION: 2022

PLW_1.2 TV HWY TO FRANCES
(CITY OF HILLSBORO)
CONSTRUCTION: 2022 - 2024

PLW_1.3 FARMINGTON TO BLANTON
(SOUTH HILLSBORO DEVELOPMENT)
CONSTRUCTION: 2022 - 2022

BEAVERTON AREA PIPELINE PROJECT
SW 209TH AVE TO WALAER RD

PLM_1.0
(PIPELINE MAIN)

5.5
MILES

CONSTRUCTION: 2021 - 2023

SCHOLLS AREA PIPELINE PROJECT
NORTH OF BEEF BEND RD TO FARMINGTON

PLM_3.0
(PIPELINE MAIN)

7.2
MILES

PLM_3.1 NORTH OF BEEF BEND TO SCHOLLS
(WASHINGTON COUNTY)
CONSTRUCTION: 2018 - 2020

PLM_3.2 SCHOLLS TO GRABHORN RD
CONSTRUCTION: 2022 - 2024

PLM_3.3 GRABHORN RD AT TILE FLAT TO FARMINGTON
CONSTRUCTION: 2022 - 2024

WILSONVILLE AREA PIPELINE PROJECT
WTP TO DAY RD

PLM_1.0
(PIPELINE MAIN)

3.0
MILES

PLM_1.1 WILSONVILLE RD
(CITY OF WILSONVILLE)
CONSTRUCTION: 2018 - 2018

PLM_1.2 GARDEN ACRES TO 124TH
(GARDEN ACRES DEVELOPMENT)
CONSTRUCTION: 2018 - 2018

PLM_1.3 WILSONVILLE RD TO GARDEN ACRES
CONSTRUCTION: 2018 - 2022

KINSMAN ROAD PARTNERSHIP PROJECT
KINSMAN RD EXTENSION

PLM_2.0
(PIPELINE MAIN)

0.5
MILES

CONSTRUCTION: 2016 - 2018
(CITY OF WILSONVILLE / ODOT)

OPPORTUNITY PROJECT
SERVICES COORDINATED WITH OTHERS

CONNECTION TO EXISTING SUPPLY LINE

Route and schedule may change.

0 1 2

March 2018

Interim Operations

- Needed during the “waiting period” between completion of package construction and 2026 startup
- Objective is to protect the pipe and lining
- Water in pipe will increase in pH
- Due to the time period, need means to document the plan and data collected

Components of the Interim Operations Plan

- Interim Operations Plan is comprised of three main components:
 - Preparation of pipe for long-term storage
 - Periodic inspection of the pipe
 - Placing of the pipe into service

Preparation of Pipe for Long-Term Storage

- Typically led by the construction contractor as required by the project specifications and consists of some or all of the following:
 - Visual inspection of the pipeline and removal of construction debris
 - Mortar coating repairs
 - Filling with water (allowing mortar to absorb)
 - Pressuring testing and disinfection per the project requirements
 - Protection/lubrication of valve seats
 - Seal pipe to keep moisture in the pipe and to keep pests/animals from entering
 - Placing into long-term storage
 - Option 1 – leave pipeline full
 - Option 2- drain most of the water



Periodic Inspection of the Pipe

- Monitoring
 - Water level/humidity
 - Water quality (e.g., pH, chlorine residual)
- Inspect valve seats and apply/reapply lubricant, where needed
- Inspect mortar lining integrity (typically at high points)
- Add water, as necessary
- Manufacturer-recommended equipment maintenance
- Re-seal pipeline
- Need to create a record of data and actions taken

Staffing Responsibilities

- Locating the pipe (requests from Oregon Utility Notification Center)
- Pipe inspections
- Sampling and water quality testing
- Equipment exercise/maintenance
- Data collection/recording

CORNELIUS PASS PIPELINE PROJECT
 FRANCES RD TO HIGHWAY 26
 PLW_2.0 (PIPELINE WEST)
3.4 MILES
 CONSTRUCTION: 2021 - 2023

SOUTH BEAVERTON AREA WATER STORAGE TANKS
 STORAGE TANKS
 RES_1.0
 CONSTRUCTION: 2022 - 2024


TUALATIN-SHERWOOD AREA PIPELINE PROJECT
 124TH AVE TO NORTH OF BEEF BEND RD
 PLM_4.0 (PIPELINE MAIN)
5.3 MILES
 PLM_A.1 HIGHWAY 99 CROSSING (WASHINGTON COUNTY) CONSTRUCTION: 2000 - 2011
 PLM_A.2 TUALATIN-SHERWOOD ROAD (WASHINGTON COUNTY) CONSTRUCTION: 2000 - 2012
 PLM_A.3 BDT ROGERS ROAD CONSTRUCTION: 2022 - 2023

124TH AVENUE PARTNERSHIP PROJECT
 SW 124TH AVE EXTENSION
 PLM_3.0 (PIPELINE MAIN)
2.7 MILES
 CONSTRUCTION: 2016 - 2018 (WASHINGTON COUNTY)

WATER TREATMENT PLANT
 WATER TREATMENT PLANT (WTP)
 WTP_1.0
 CONSTRUCTION: 2022 - 2025
 INCLUDES FINISHED WATER PUMP-STATION PROJECT (EPL_3.0)
 INCLUDES DISTRIBUTED CONTROL SYSTEM PROJECT (ECS_3.0)

RAW WATER FACILITIES
 RAW WATER FACILITIES (RAW)
 RAWF_1.0
 CONSTRUCTION: 2020 - 2024

Willamette Water Supply
Our Reliable Water
 PROJECTS



SOUTH HILLSBORO AREA PIPELINE PROJECT
 FARMINGTON RD TO FRANCES RD
 PLW_1.0 (PIPELINE WEST)
3.9 MILES
 PLW_1.1 BLANTON TO TV HWY (SOUTH HILLSBORO DEVELOPMENT) CONSTRUCTION: 2022
 PLW_1.2 TV HWY TO FRANCES (CITY OF HILLSBORO) CONSTRUCTION: 2022 - 2024
 PLW_1.3 FARMINGTON TO BLANTON (SOUTH HILLSBORO DEVELOPMENT) CONSTRUCTION: 2022 - 2022

BEAVERTON AREA PIPELINE PROJECT
 SW 20TH AVE TO WALAER RD
 PLE_1.0 (PIPELINE EAST)
5.5 MILES
 CONSTRUCTION: 2021 - 2023


SCHOLLS AREA PIPELINE PROJECT
 NORTH OF BEEF BEND RD TO FARMINGTON
 PLM_5.0 (PIPELINE MAIN)
7.2 MILES
 PLM_5.1 NORTH OF BEEF BEND TO SCHOLLS (WASHINGTON COUNTY) CONSTRUCTION: 2018 - 2020
 PLM_5.2 SCHOLLS TO GRABHORN RD CONSTRUCTION: 2022 - 2024
 PLM_5.3 GRABHORN RD AT TILE FLAT TO FARMINGTON CONSTRUCTION: 2022 - 2024

WILSONVILLE AREA PIPELINE PROJECT
 WTP TO DAY RD
 PLM_1.0 (PIPELINE MAIN)
3.0 MILES
 PLM_1.1 WILSONVILLE RD (CITY OF WILSONVILLE) CONSTRUCTION: 2022 - 2022
 PLM_1.2 GARDEN ACRES TO 124TH (GARDEN ACRES DEVELOPMENT) CONSTRUCTION: 2022 - 2022
 PLM_1.3 WILSONVILLE RD TO GARDEN ACRES CONSTRUCTION: 2020 - 2022

KINSMAN ROAD PARTNERSHIP PROJECT
 KINSMAN RD EXTENSION
 PLM_2.0 (PIPELINE MAIN)
0.5 MILES
 CONSTRUCTION: 2016 - 2018 (CITY OF WILSONVILLE / ODOT)

OPPORTUNITY PROJECT (SHOWN COORDINATED WITH OTHERS)
 CONNECTION TO EXISTING SUPPLY LINE
 Route and schedule may change.
 0 1 2
 March 2018

PLW_1.1 Profile



Interim Operations Plan Development for PLW_1.1

July 2017

- Advance Interim Plan Development
- Identify Issues to Resolve

August 2017

- Review Draft Interim Operations Plan for PLW_1.1 and SOPs
- Define Responsibilities and Ongoing Coordination Approach
- Site Visit to Review Installation

September 2017

- Finalize Interim Operations Plan
- Finalize Responsibilities and Ongoing Coordination Approach

October 2017

- Confirm Readiness to Implement Plans

PLW_1.1 Interim Storage and Operations Specifics

- PLW_1.1 to be placed in storage for approximately one year (with pipe left full of water)
- Monitoring and maintenance required for the year
- After one year, City of Hillsboro to place PLW_1.1 pipe into service

Organizational Responsibilities

WWSP

- Startup Coordination and Management
- Training of interested parties
- Prepare and Update Interim Plan
- Manage Data Storage and Analysis
- Lead Facilitation and Coordination
- Prepare Overall Operations Plan

Hillsboro

- Operate PLW_1.1 (between main line valves), operate and maintain STL valve, operate TV Hwy vaults, operate and maintain Blanton vault (share meter data with WWSP/TVWD)
- Provide Data and Feedback to WWSP
- Participate in Ongoing Coordination/Communication
- Participate in Overall Operations Plan Development

Definitions:

Operate

- Water quality sampling and testing
- Flow and pressure management

Maintain

- Preventative maintenance
- Repairs
- Collecting asset performance data
- Turning valves
- Warranty management and inspection
- Spare parts storage/inventory

TVWD

- Complete all locates
- Operate and Maintain PLW_1.1 (dead ends), Maintain PLW_1.1 (line valves and air valves between main line valves with direction from COH), maintain TV Hwy vaults (with direction from COH)
- Provide Data and Feedback to WWSP
- Participate in Ongoing Coordination/Communication
- Participate in Overall Operations Plan Development

PLW_1.1 Preliminary Operations Plan


Action	Frequency	Date	Responsibility	Status/Notes
Prior to Final Completion				
Establish schedule	N/A	N/A	N/A	Pipe testing Third week of August, 2017 Substantial completion October 20, 2017 Final completion November 20, 2017
Design sample stations	N/A	7/24/17	Corianne H/KJ	COMPLETE
Design "jumper" to keep pipe pressurized for sampling	N/A	8/15/17	Corianne H/KJ	Need to consider how jumper will be removed at a later date. Leave jumper open or provided above-ground access to the valve to ensure WQ staff does not need to enter a confined space. Consider meter to measure flow into the pipe as an indication of leakage.
Install "jumper"	N/A	9/15/17	Kerr	
Determine regular maintenance to be completed and maintenance intervals	N/A	9/15/17	Corianne H	Look at OM for exercising valves, inspections, battery life, manufacturer's recommendations, etc.
Install sample stations	N/A	10/1/17	Kerr	Piping has been installed, still need to install sample boxes
Submit polygons of final as-builts to One Call at substantial completion	N/A	10/20/17	Scott F	
Fill pipe with water	N/A	10/20/17	Kerr	Contractor will pressure test, drain, and then refill prior to substantial completion
Start collecting WQ samples	Weekly initially, less as readings stabilize	10/20/17	Jessica D	WQ testing includes pH, chlorine residual, heterotrophic plate counts, conductivity, alkalinity, and oxygen reduction potential
After Final Completion				
Locating of pipe	N/A	10/20/17	TVWD	Through One Call system
Monitor water level in pipe	N/A	N/A	City of Hillsboro	Use meter on jumper to monitor drops in pressure as an indication of water being added to the pipe

Issues Identified During Planning




- Sampling stations required for safety of water quality staff (high pH water, limit confined space entries)
- Lubrication of valve seats not required due to water in the pipe
- Inspection/sampling frequency developed
- Need source to add water (approximately 50,000 gallons)
- Data to record (water quality parameters, actions, date, responsibility, status)
- Identified potential for dead zones in pipe during City of Hillsboro operations

Sample Station




2 SAMPLE STATION INSTALLATION
COH STD DWG WTR-50 NTS



Standard Operating Procedures Developed

- Confined space entry
- Pipe locating
- Water quality sampling
- Water quality data collection
- Water level verification
- Maintenance of equipment

Water Quality



Water Quality

- Where did we end up?

Parameter	Q1						Q2 ²	Q3 ²	Q4 ²
	Week 1 ¹		Week 2	Week 3	Week 4	Month 2			
pH	x	x	x	x	x	x	x	x	x
Conductivity	x	x	x	x	x	x	x	x	x
Coliform/ <i>E. coli</i>	x			x		x	x		x
Total, free chlorine ³	x	x	x	x	x				
HPC	x			x		x	x	x	x
Alkalinity	x			x		x	x	x	x
ORP	x	x	x	x	x	x	x	x	x
Temperature	x	x	x	x	x	x	x	x	x

What's Next?



Thank you!

Matthew Gribbins

matt.gribbins@tvwd.org

Joel Cary

joel.cary@tvwd.org

Marlys Mock

Media & Community Relations Coordinator

Willamette Water Supply Program

503-941-4570

info@ourreliablewater.org

www.ourreliablewater.org



2018 TACOMA PNWS-AWWA

