

Willamette Water Supply
Our Reliable Water



2018 TACOMA PNWS-AWWA

Taking a test drive – How physical modeling can help achieve optimal performance and maximize existing infrastructure

April 26, 2018

Acknowledgements

- Mike Britch, P.E. – WWSP
- Matthew Gribbins, P.E. – WWSP
- Darren Hinton, P.E., Ph.D – NHC
- Thomas Demlow, M.S., P.E. – NHC

Agenda

- Project background
- Physical model testing plan
- Results
- Conclusions and next steps

PROJECT BACKGROUND

WWSP Program Components

- Modified water intake
- New water filtration plant
- Water reservoirs
- 30+ miles of large diameter pipeline




Raw Water Facilities (RWF_1.0) Background



Expansion of existing raw water facilities at
the WRWTP



RWF Project Timeline



Existing Infrastructure Sized for Expansion



SECTION A
1/4"=1'-0" 2M-01

Existing Raw Water Pump Station




Physical Modeling Provides Confidence to System Owners

- Original capacity of 120 mgd
- Desired capacity of 150 mgd
- CFD modeling indicates pumps do not meet all Hydraulic Institute (HI) metrics
- Potential solution identified
- HI ANSI 9.8 recommends physical model for pump station with flows over 100,000 gpm or 144 mgd



Computational Fluid Dynamic Modeling of Proposed Upgrade

- Used for preliminary hydraulic evaluation
- Found no fatal flaws with pump intake hydraulics



Constraints of Existing Infrastructure

- Existing plant must maintain operations
- Need seismically resilient solution
- Structural changes are challenging



Pre-Work to Inform Physical Model

- Survey of existing infrastructure
- Calculation of screen losses




PHYSICAL MODEL TESTING PLAN

Objectives

- Determine if wet well provides satisfactory approach flow that meets 2012 ANSI/Hydraulic Institute (HI) 9.8 Pump Intake Design Standard
- If approach flow does not meet the HI Standard, then develop modifications to produce acceptable flow to the pumps

Check Hydraulic Institute Standards for Problematic Pump Intake Conditions

- Vortex formation
- Air entrainment
- Pre-swirl
- Non-uniform velocity distribution at impeller
- Excessive turbulence at impeller



Hydraulic Conditions Evaluated with a Scale Physical Model

- Model Recommendations

- Free Water Surface:

- >100,000 gpm total flow
 - >40,000 gpm pump flow
 - >5,000 gpm pump flow circular wetwell

- Closed Conduit Pump Applications:

- >5,000-10,000 gpm pump flow

- Model Scale Requirements:

- F = 1:1
 - E: OK if R and W met
 - $R > 6.4 \times 10^2$
 - $W > 240$

Froude Number $F = \frac{U}{\sqrt{gL}} = \frac{\text{Inertial Force}}{\text{Gravity Force}}$

Euler Number $E = \frac{\Delta P}{\rho U^2} = \frac{\text{Pressure Force}}{\text{Inertial Force}}$

Reynolds Number $R = \frac{UL}{\nu} = \frac{\text{Inertial Force}}{\text{Viscous Force}}$

Weber Number $W = \frac{U}{\sqrt{\frac{\sigma}{\rho L}}} = \frac{\text{Inertial Force}}{\text{Surface Tension Force}}$

where: U = characteristic flow velocity
g = gravitational acceleration
L = characteristic length
ρ = density of fluid
ΔP = pressure difference
ν = kinematic fluid viscosity
σ = surface tension of the fluid

HI Model Pump Performance Criteria

- Velocity within $\pm 10\%$ of mean at pump throat
- Turbulence intensity less than 10%
- Flow swirl less than 5 degrees from axial
- Minimal vortex activity




1 to 5 Scale Selected Based on Typical Pumps for the Planned Operation


- 26-inch Bells at 13.3 mgd
- 31-inch Bells at 19.5 mgd

Pump	Reynolds (bell)	Weber
Willamette 28MKM	1.1×10^5	1,330
Willamette 23TKH	1.0×10^5	1,320
Willamette 23TKM	9.0×10^4	1,040

Model Layout



Model Layout



Model Construction



Physical Model Test Conditions

Test No.	Water Level in Wet Well	Operating Pumps, mgd										Total Pump Station Discharge	
		Wet Well											
	(ft)	28MKM1	28MKM2	28MKM3	28MKM4	28MKM5	23TKH1	23TKH2	23TKH3	23TKM1	23TKM2	(mgd)	
Initial Design Testing ^a	ID1	52.7	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	150.0
	ID2	52.7	-	18.00	18.50	18.50	18.50	13.30	13.30	13.30	13.30	13.30	140.0
	ID3	55.0	-	-	-	-	10.00	-	-	7.50	-	7.00	24.5
	ID4	52.7	-	-	-	-	19.60	-	-	15.00	13.30	-	47.9
	ID5	52.7	19.60	19.60	19.60	-	19.60	15.00	15.00	15.00	13.30	13.30	150.0
Design Development Testing ^b	DD	52.7	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	150.0
Ultimate Capacity Testing	UC1	TBD ^c	-	Initial design testing						30	13.30	13.30	140.0
	UC2	52.7	-	Initial design testing						00	13.30	13.30	TBD ^d
Final Documentation Testing	FD1	52.7	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	150.0
	FD2	52.7	19.60	19.60	19.60	-	19.60	15.00	15.00	15.00	13.30	13.30	150.0
	FD3	52.7	19.60	-	19.60	19.60	19.60	15.00	15.00	-	13.30	13.30	135.0
	FD4	55.0	19.60	-	19.60	19.60	19.60	-	15.00	15.00	13.30	13.30	135.0
	FD5	52.7	19.60	-	-	19.60	19.60	15.00	15.00	-	-	13.30	102.1
	FD6	52.7	19.60	19.60	-	-	19.60	15.00	15.00	-	-	13.30	102.1
	FD7	52.7	19.60	-	19.60	-	-	-	15.00	-	-	13.30	67.5
	FD8	52.7	-	-	19.60	-	19.60	-	-	15.00	13.30	-	67.5
	FD9	52.7	-	-	19.60	19.60	-	-	15.00	-	-	-	54.2
	FD10	55.0	-	-	-	-	10.00	-	-	7.50	-	7.00	24.5
	FD11	52.7	Max	Max	Max	Max	Max	Max	-	-	-	-	131.0
	FD12	55.0	Max	Max	Max	Max	Max	Max	Max	Max	Max	Max	Max

Physical Model Test Conditions

Test No.	Water Level in Wet Well (ft)	Operating Pumps, mgd										Total Pump Station Discharge (mgd)	
		Wet Well											
		28MKM1	28MKM2	28MKM3	28MKM4	28MKM5	23TKH1	23TKH2	23TKH3	23TKM1	23TKM2		
Initial Design Testing ^a	ID1	52.7	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	150.0
	ID2	52.7	-	18.00	18.50	18.50	18.50	13.30	13.30	13.30	13.30	13.30	140.0
	ID3	55.0	-	-	-	-	10.00	-	-	7.50	-	7.00	24.5
	ID4	52.7	-	-	-	-	19.60	-	-	15.00	13.30	-	47.9
	ID5	52.7	19.60	19.60	19.60	-	19.60	15.00	15.00	15.00	13.30	13.30	150.0
Design Development Testing ^b	DD	52.7	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	150.0
Ultimate Capacity Testing	UC1	TBD ^c	-	18.00	18.50	18.50	18.50	13.30	13.30	13.30	13.30	13.30	140.0
	UC2	52.7	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	TBD ^d
Final Documentation Testing	FD1	52.7	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	150.0
	FD2	52.7	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	150.0
	FD3	52.7	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	135.0
	FD4	55.0	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	135.0
	FD5	52.7	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	102.1
	FD6	52.7	42.00	42.00	-	-	42.00	42.00	42.00	-	-	13.30	102.1
	FD7	52.7	19.60	-	19.60	-	-	-	15.00	-	-	13.30	67.5
	FD8	52.7	-	-	19.60	-	19.60	-	-	15.00	13.30	-	67.5
	FD9	52.7	-	-	19.60	19.60	-	-	15.00	-	-	-	54.2
	FD10	55.0	-	-	-	-	10.00	-	-	7.50	-	7.00	24.5
	FD11	52.7	Max	Max	Max	Max	Max	-	-	-	-	-	131.0
	FD12	55.0	Max	Max	Max	Max	Max	Max	Max	Max	Max	Max	Max

Design development testing

Physical Model Test Conditions

Test No.	Water Level in Wet Well (ft)	Operating Pumps, mgd										Total Pump Station Discharge (mgd)		
		Wet Well												
		28MKM1	28MKM2	28MKM3	28MKM4	28MKM5	23TKH1	23TKH2	23TKH3	23TKM1	23TKM2			
Initial Design Testing ^a	ID1	52.7	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	150.0	
	ID2	52.7	-	18.00	18.50	18.50	18.50	13.30	13.30	13.30	13.30	13.30	140.0	
	ID3	55.0	-	-	-	-	10.00	-	-	7.50	-	7.00	24.5	
	ID4	52.7	-	-	-	-	19.60	-	-	15.00	13.30	-	47.9	
	ID5	52.7	19.60	19.60	19.60	-	19.60	15.00	15.00	15.00	13.30	13.30	150.0	
Design Development Testing ^b	DD	52.7	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	150.0	
Ultimate Capacity Testing	UC1	TBD ^d	-	18.00	18.50	18.50	18.50	13.30	13.30	13.30	13.30	13.30	140.0	
	UC2	52.7	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	TBD ^d	
Final Documentation Testing	FD1	52.7	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	150.0	
	FD2	52.7	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	150.0	
	FD3	52.7	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	135.0	
	FD4	55.0	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	135.0	
	FD5	52.7	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	102.1	
	FD6	52.7	49.00	49.00	-	-	49.00	49.00	49.00	49.00	-	-	13.30	102.1
	FD7	52.7	19.60	-	19.60	-	-	-	15.00	-	-	13.30	67.5	
	FD8	52.7	-	-	19.60	-	19.60	-	-	15.00	13.30	-	67.5	
	FD9	52.7	-	-	19.60	19.60	-	-	15.00	-	-	-	54.2	
	FD10	55.0	-	-	-	-	10.00	-	-	7.50	-	7.00	24.5	
	FD11	52.7	Max	Max	Max	Max	Max	-	-	-	-	-	131.0	
	FD12	55.0	Max	Max	Max	Max	Max	Max	Max	Max	Max	Max	Max	

Ultimate capacity testing

Physical Model Test Conditions


Test No.	Water Level in Wet Well (ft)	Operating Pumps, mgd										Total Pump Station Discharge (mgd)		
		Wet Well												
		28MKM1	28MKM2	28MKM3	28MKM4	28MKM5	23TKH1	23TKH2	23TKH3	23TKM1	23TKM2			
Initial Design Testing ^a	ID1	52.7	-	19.60	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	150.0
	ID2	52.7	-	18.00	18.50	18.50	18.50	18.50	13.30	13.30	13.30	13.30	13.30	140.0
	ID3	55.0	-	-	-	-	-	-	-	-	-	-	7.00	24.5
	ID4	52.7	-	-	-	-	-	-	-	-	-	-	-	47.9
	ID5	52.7	-	-	-	-	-	-	-	-	-	13.30	13.30	150.0
Design Development Testing ^b	DD	52.7	-	-	-	-	-	-	-	-	-	13.30	13.30	150.0
Ultimate Capacity Testing	UC1	TBD ^c	-	-	-	-	-	-	-	-	-	-	-	-
	UC2	52.7	-	19.60	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	TBD ^d
Final Documentation Testing	FD1	52.7	-	19.60	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	150.0
	FD2	52.7	19.60	19.60	19.60	-	19.60	19.60	15.00	15.00	15.00	13.30	13.30	150.0
	FD3	52.7	19.60	-	19.60	19.60	19.60	19.60	15.00	15.00	-	13.30	13.30	135.0
	FD4	55.0	19.60	-	19.60	19.60	19.60	19.60	15.00	15.00	15.00	13.30	13.30	135.0
	FD5	52.7	19.60	-	-	19.60	19.60	19.60	15.00	15.00	-	-	13.30	102.1
	FD6	52.7	19.60	19.60	-	-	19.60	19.60	15.00	15.00	-	-	13.30	102.1
	FD7	52.7	19.60	-	19.60	-	-	-	-	15.00	-	-	13.30	67.5
	FD8	52.7	-	-	19.60	-	19.60	19.60	-	-	15.00	13.30	-	67.5
	FD9	52.7	-	-	19.60	19.60	-	-	-	15.00	-	-	-	54.2
	FD10	55.0	-	-	-	-	-	10.00	-	-	7.50	-	7.00	24.5
	FD11	52.7	Max	Max	Max	Max	Max	Max	-	-	-	-	-	131.0
	FD12	55.0	Max	Max	Max	Max	Max	Max	Max	Max	Max	Max	Max	Max

Witness test followed by Documentation testing

RESULTS


Initial Test Results - Swirl

- Flow pre-swirl too high
 - 12° average, 14° maximum
 - Effective rotation difference leads to cavitation
 - Deviation from best efficiency point



Initial Test Results, Continued

- Strong Type 2 Vortex Formation
 - Low pressure point leads to localized cavitation
 - Potential air entrainment



Initial Test Results - Velocity and Turbulence

- Velocity distribution is OK
- Excessive turbulence at impeller
 - Up to 26%
 - Shaft and bearing problems
 - Cavitation
 - Impeller blade fatigue



Recommended Improvements

- Flow conditioning baskets
 - Uniform flow entering pump
 - Optimization of pump performance
 - HI criteria met
 - Extend equipment life
 - Limited shutdown for installation




RWF_1.0 Physical Model Witness Test



Flow Conditioning Baskets Addressed Pump Hydraulics

- Vortex's eliminated
- Swirl reduced to maximum of 3°
- Maximum turbulence reduced to 10%
- Maximum Capacity of 196 mgd tested
- Additional Bell Sizes Tested



CONCLUSIONS AND NEXT STEPS

Conclusions and Next Steps

- Physical modeling provided needed flow validation for system Owners
- Optimization of existing infrastructure beyond original anticipated capacity
- Basket details will be included in final design suitable for a range of pumps

Thank you!

Ed Wicklein

Carollo Engineers, Inc.

Ewicklein@carollo.com

Jenn Minton

Raw Water Facilities Project Manager

Willamette Water Supply Program

503-941-4585

info@ourreliablewater.org

www.ourreliablewater.org



2018 TACOMA PNWS-AWWA

